Item No.	Description of work	Unit	Quantity
15	Constructing cornice 12″ deep as per existing design and specification ..	R.ft.	304
16	Band cornice as per existing design	,,	304
17	Boxing girders as per specification in Ground Floor	,,	324
18	$4\frac{1}{2}'' \times 1\frac{1}{2}''$ mortar architrave finish around arches	,,	264
19	Ornamental finish	L. S.	
20	Providing balastrated parapet 3′ high as per existing design complete.	R.ft.	120
21	Providing plain parapet wall as per existing design	,,	181
22	Providing rain water down pipes of cast iron including C.I. gratings, heads, bends, etc., complete	,,	570
23	Constructing dome with necessary girders, etc., as per existing arc ..	L. S.	
	ALTERNATIVE ITEMS OF WORK.		
1	Providing rain water down pipes of cement asbestos 4″ dia. including bends, etc., and fixing complete	R.ft.	570
2	Painting 2 coats with Government Lac Factory green paint	Sqr.	—
3	Painting 3 coats with Government Lac Factory Lac polish, including scraping, sand papering, etc., complete	Sqr.	—
4	Reinforced cement concrete shell for dome as per existing design ..	C.ft.	—

M. A. RAMANUJAM,
Assistant Engineer.

CHITALDRUG DIVISION.

Notice dated 14th July 1939.

Sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 5th August 1939, for Raising the weirs constructing lifting Dam across the weir hallah and other works of Chik Madhure Tank, Challakere Taluk.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for Raising the weirs constructing, lifting Dam across the weir hallah and other works of Chik Madhure Tank, Challakere Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 630 (Rupees six hundred and thirty only) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 5th August 1939 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Re. 1.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 10 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Lumpsum item of work will paid after taking detailed measurements.
24. Chamundi Brand cement alone to be used.

Abstract estimate for raising the Waste Weirs, constructing a Lifting Dam across the Waste Weir halla and other works of Chickamadhure Tank, Challakere Taluk.

Sl. No.	Items of work	Unit	Quantity	Rate	In figures	In words
				Rs. a. p.		
	1. CONSTRUCTING THE PROPOSED LIFTING DAM ACROSS THE WEIR HALLA.					
1	Earthwork cutting open the existing groyne and refilling with watering and tamping on finishing the masonry work in this portion	C.yd.	20	0 5 0		
2	Earthwork excavation for foundation, etc., Hard Chettu Soil and Soft Rock	,,	163	0 7 0		
3	Earthwork putting the proposed bund along with the regulating wall across the lifting dam with perfect consolidation (using the good earth available from excavation in the dam work as well as in the bed of the apron of left weir close by) only consolidation and lead charge	,,	200	0 2 0		
4	New stone revetment with jelly including a lead of two to three miles	,,	90	1 12 0		
5	Gravel backing to the rough stone revetment.	,,	32	0 8 0		
6	Removing and resetting old stone revetment.	,,	5	0 12 0		
7	Burnt brick in Surki mortar	C.ft.	1,091	0 5 0		
8	Surki mortar plastering	Sqr.	4·48	4 0 0		
9	Burnt stone slabs dressed 6" thick	S.ft.	408	0 12 0		
10	Joggle joints to coping slabs	Each	13	0 12 0		
11	Constructing new stone apron with jelly including a lead of two to three miles	C.yd.	34	1 12 0		
12	Clearing draft hard soil	,,	33	0 6 0		
	2. RAISING THE LEFT WEIR.					
1	Earthwork excavation for foundation, etc., (partly hard soil and soft and hard rock).	C.yd.	213	0 8 0		
2	Earthwork putting to flank bund with perfect consolidation (using the earth available from excavation and clearing draft, etc.,) only lead and consolidation charge	,,	35	0 1 6		
3	New stone revetment with jelly including a lead of two to three miles	,,	25	1 12 0		
4	Removing and resetting old stone revetment.	,,	5	0 12 0		
5	Gravel backing to stone revetment	,,	11	0 8 0		
6	Filling the seat of apron (with consolidation earth available from excavation from seating the apron draft clearing) only consolidation charges	C.yd.	38	0 1 6		
7	Burnt brick in Surki mortar	C.ft.	763	0 5 0		
8	Surki mortar plastering	Sqr.	3·67	4 0 0		
9	Burnt stone slabs dressed 6" thick	S.ft.	506	0 12 0		
10	Joggle joints to the body wall coping slabs, etc.	Each	22	0 12 0		
11	Constructing new stone apron with jelly	C.yds.	175	1 12 0		
12	Dismantling the top layer of existing brick masonry					
13	Fixing the gauge stone pillar in proper position					
14	Cutting draft in the weir, hard soil and partly hard and soft rock	C.yd.	157	0 7 0		
	3. RAISING THE RIGHT WEIR.					
1	Earthwork excavation for foundation, etc., (soft rock and partly hard and soft rock).	C.yd.	280	0 7 0		
2	Filling in the seat of apron (with jelly and earth available from excavation in the same weir). Only lead and consolidation charges	C.yd.	71	0 1 6		

Sl. No.	Items of work	Unit	Quantity	Rate	In figures	In words
				Rs. a. p.		
3	Burnt brick in Surki mortar	C.ft.	1,026	0 5 0		
4	Surki mortar plastering	Sqr.	5·00	4 0 0		
5	Burnt stone slabs dressed (6″ thick) ..	S.ft.	909	0 12 0		
6	Conveying and fixing old stone slabs available	,,	121	0 4 0		
7	Dismantling top layer of existing brick masonry	(As per actual measurements).				
8	Construction of new stone apron with jelly filling including lead of two to three miles.	C.yd.	218	1 12 0		
9	Joggle joints to coping slabs	Each	52	0 12 0		
10	Clearing draft in the approach as well as beyond the apron (soft rock and partly hard rock) and also the natural ground weir site (front and rear)	C.yd.	723	0 7 0		
	4. EXTENDING THE SLUICE TUNNEL ACROSS THE APRON OF RIGHT WEIR.					
	Earthwork excavation for foundation, etc., (soft rock)	C.yd.	24	0 7 0		
2	Surki mortar concrete (with stone jelly and Surki mortar)	C.ft.	138	0 4 6		
3	Burnt brick in Surki mortar	,,	95	0 5 0		
4	Surki mortar plastering	Sqr.	1·71	4 0 0		
5	Burnt stone slabs 6″ thick dressed	S.ft.	75	0 12 0		
	5. SILT CLEARING THE LEFT SLUICE CHANNEL.					
1	Silt clearing in the left sluice channel from 6/2 to 9th Madaboy	C.yd.	623	0 2 0		
	6. PUTTING UP BEAM UP TO THE LEVEL OF INTERSECTION OF SATURATION GRADIENT 1 IN 4.					
1	Earthwork to bund including watering and tamping. Saturation gradient 1 : 4 from M.W.L. 63·25 (20 feet lift and lead up to one furlong)	C.yd.	4,348	0 6 0		
2	Turfing the slopes of bund	S.yd.	1,092	0 1 0		

S. RAMASWAMY,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated* 19*th November* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

GOVERNMENT HIGH SCHOOL, FORT, BANGALORE.

Notice No. 96, *dated* 14*th July* 1939.

A sum of Rs. 4-2-0 being the scholarship of Shafi Ahamed Sheriff, a student of the High School First year class (D) of this High School for February and March 1939 remaining undisbursed. He should prefer his claim within 30 days from this date. Otherwise the amount will be remitted to the Treasury and no claim will be considered.

M. A. NARAYANA IYENGAR,
Head-Master.